BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED

SECTION 9

Bill of Quantities (BoQ)

PART I : Supply Portion

Sl. No.	Particulars	Unit	Material Code	Total Qty
1	12Way HRC Fuse Switch based Thermo setting Plastic LT Feeder Pillar Box	No.	300314	1409
2	240Sq.mm Heavy Duty Copper Terminal Long barrel Apprx Wt.218Gm	No.	288536	4762
3	50 Sq.mm Heavy Duty Copper Terminal Long barrel Apprx Wt.26Gm	No.	288529	11272
4	25 Sq.mm Heavy Duty Copper Terminal Long barrel , Apprx Wt.11Gm	No.	288527	28180
5	Epoxy Terminating Kit (Pothead) Suitable for 1.1kV LT U.G.Cable 3.5 X 225/240/300 Sq.mm	Set	288165	972
6	Epoxy Terminating Kit (Pothead) Suitable for 1.1kV LT U.G.Cable upto 4C X 50 Sq.mm (50 Sq.mm)	Set	288150	972
7	Epoxy Terminating Kit (Pothead) Suitable for 1.1kV LT U.G.Cable upto 4C X 50 Sq.mm (25 Sq.mm)	Set	288150	2430
8	Vermin proof for Feeder Pillar Box	LS		1409
9	Earthing Materials, GI Pipe type for Grounding, Complete set (as per Sl.no 7 of Cost Data sheet 26 of SR-2023-24)	Set	281674, 600095, 607054	1409

PART II : Erection Portion

Sl.No.	Particulars	Unit	Total Qty.
1	Installation and commissioning of 12Way HRC Fuse Switch based Thermo setting Plastic LT Feeder Pillar Box	No.	1409
2	Providing 240Sq.mm Heavy Duty Copper Terminal Long barrel Apprx Wt.218Gm	No.	4762
3	Providing 50 Sq.mm Heavy Duty Copper Terminal Long barrel Apprx Wt.26Gm	No.	11272
4	Providing 25 Sq.mm Heavy Duty Copper Terminal Long barrel , Apprx Wt.11Gm	No.	28180
5	Providing Epoxy Terminating Kit (Pothead) Suitable for 1.1kV LT U.G.Cable 3.5 X 225/240/300 Sq.mm	Set	972
6	Providing Epoxy Terminating Kit (Pothead) Suitable for 1.1kV LT U.G.Cable upto 4C X 50 Sq.mm (50 Sq.mm)	Set	972
7	Providing Epoxy Terminating Kit (Pothead) Suitable for 1.1kV LT U.G.Cable upto 4C X 50 Sq.mm (25 Sq.mm)	Set	2430
8	Vermin proofing for Feeder Pillar Box	LS	1409
9	Providing Earthing Materials, GI Pipe type for Grounding, Complete set (as per Sl.no 7 of Cost Data sheet 26 of SR-2023-24)	Set	1409
10	Dismantling of Existing deteriorated conventional type (Metal) LT Feeder pillar Boxes	No.	923

-Sd-

General

DAS, Smart

Manager (Ele)

Grid & TIC